



التاريخ: 2021/11/16

محضر اجتماع لجنة العطاءات المركزية

فتح مظاريف إعادة طرح العطاء رقم 2021 /93

توريد مشروع تكييف قسم العمليات في مستشفى بيت حانون لصالح وزارة

الصحة

اجتمعت لجنة العطاءات المركزية اليوم الثلاثاء الموافق 2021/11/16 م وفي تمام الساعة الحادي عشر صباحاً بحضور كلاً من:

- | | |
|---|----------------------------|
| رئيساً - لجنة العطاءات المركزية | 1. السيد / أحمد حسن الشنطي |
| عضواً - لجنة العطاءات المركزية | 2. السيد / جبر حجازي |
| عضواً - لجنة العطاءات المركزية | 3. السيد / أيمن الخالدي |
| عضواً - لجنة العطاءات المركزية | 4. السيدة/ فاطمة عوض |
| عضو مراقب - ديوان الرقابة الإدارية والمالية | 5. السيد / إيهاب الرئيس |

وذلك في مقر الإدارة العامة للوزراء بوزارة المالية في غزة .
أعمال اللجنة :

تم فتح صندوق العطاءات بحضور الشركات المتقدمة للعطاء ووجد بداخله عدد (1) مظاريف .
قامت اللجنة بتقييمها وفتحها وإثبات حالتها وقراءة الأسعار أمام الحضور، والجدول التالي يوضح أسماء الشركات المتقدمة وقيمة العروض المتقدمة بها وأسعارها:

م.	اسم الشركة	ملاحظات
	شركة طلال مرتجي	حسب الكشف المرفق



كشف تفريغ كفالة دخول العطاء:

ملاحظات	تاريخ الانتهاء	تاريخ الإصدار	اسم البنك	نوعها	قيمة الكفالة	اسم الشركة	م.
-	2022/12/5	2021/11/07	البنك الوطني	كفالة بنكية	15000 شيكل	شركة طلال مرتجى	1



تم تفريغ الأسعار حسب الجدول التالي:

No.	Description	Unit	Qu	1/1 شركة طلال مرتجي السعر بالدولار
	Note :1			
	All following items shall be executed according to drawings, specifications and as directed by the Engineer. Prices shall include all required works, fittings , connections , accessories and testing.			
	Note :2			
	Contractor shall submit shop drawings for all Mechanical installations to be approved by the Engineer before executing the work. As-made drawings shall be submitted after completing the work			
1	HVAC works			
1.1	Supply, install and commission outdoor Variable Refrigerant Flow (VRF) heat pump air conditioning sets based on refrigerant R410 with highly efficient scroll compressors with all inverter type compressors(Full DC inverter modle), special acryl pre coated heat exchanger, low noise condenser fan, pre coated fin type heat exchangers. The outdoor and indoor units shall be integrated with special super wiring system with a central monitoring remote controller into one common wiring , Daikin or EQ last version. The price include control system and to be established to BMS (with Mini BMS features): Centralized controller, Network control and monitoring access,			



	<p>PC control software, Group control, Individual control, Mode selection, Fan speed control, Temperature control, Mode lock, Remote controller lock and keyboard lock), G. steel bases, copper refenets and fittings and “ Y “ connections for indoor and outdoor units according to the manufacturer instructions and design , gas pipes from outdoor units to AHU (Price shall include all copper pipes works), in addition to headers and pipes branches and all accessories needed to complete the job,the models must be have EuroVent,CE certified and COP not less than 4.5</p> <p>The price shall also include electrical cables and connection to main distribution boards ,water proof maintenance isolator switch .</p>			
1.1.1	Outdoor Group-1 Cooling Capacity 38.6 KW (132000BTU/HR)	No.	2	16000



No.	Description	Unit	Qu	1/1 شركة طلال مرتجي السعر بالدولار
1.2	<p>Air Handling Units :</p> <p>Supply, left to position, install, test & commission, Daikin or EQ , Air Handling Unit , high static pressure centrifugal fan ,Electrical Heater , (Dx) type copper air cooling coil with Aluminum fins special acryl pre coated and connected to separated air cooled condensing unit , air humidifying chamber with separated variable electrical water vapor generation unit , H14 HEPA filter 99.995%, bag filters, panel filters, high static pressure variable speed fan, double skin cover with internal cladding, stainless steel condensate water collector and drain, filters dirtiness sensors, indoor & in unit differential pressure & (DB/WB) temperature sensors, PLC with touchable HMI screen, electrical protection panel (overload protection and magnetic contactor), drain pipes with insulation up to nearest, indoor temperatures control panel with digital screen & temperatures sensors, motorized volume dampers, wiring works, all low voltage & signal connections, training of two technicians, supports, hangers , The AHU should be outside door fit, made of galvanized steel not less than 0.80 mm, and be treated for external sea weather</p> <p>Price must also include all needed Pipes network to be conected to chiler with its thermal insulation and all required fitting ,equipment to start the system</p> <p>All works done according to specifications, drawings & standards and Engineer satisfaction.</p>			
1.2.1	<p>AHU11.0 TR Cooling Capacity, (1000 CFM), without Electrical Heater and humidifier, Condensing Unit (VRF)</p>	No.	2	11000



No.	Description	Unit	Qu	1/1 شركة طلال مرتجى السعر بالدولار
1.3	<p>Semi Central unit (5 TR)</p> <p>Supply , install, test and commission air conditioning Heat Pumpsemi central unit,1400 cfm, tornado type , composed of out door unit. filled with environment friendly refrigerant such as (R410, R407c,..) and COP not less than 3.5, .Well supported on galvanized steel base on the roof, indoor unit roof mounted as indicated on drawings with mixing box , to be tights installed completed with all necessary supports , dust filter , hangers, drain pipes from indoor unit to the nearest floor drain (PVC Ø 2"), cupper pipes, sleeves, thermostat, with fresh air, humidity controlling, insulation, aluminum foil, the price must incuding HEPA filter H14 have static pressure less than 350 PA, Differential pressure sensor after and before HEPA filter, s.steel 316L blower fan and all related work and all required electrical cables according to standards and drawings and engineers approval</p> <p>CAPACITY : (600000 btu / hr)</p>	No.	1	4000



No.	Description	Unit	Qu	1/1 شركة طلال مرتجى السعر بالدولار
1.4	<p>Split Unit (1 TR)</p> <p>Supply , install, test and commission air conditioning Heat Pump Split Unit, tornado type , composed of out door unit. filled with environment friendly refrigerant such as (R410, R407c,..) and COP not less than 3.5, Well supported on galvanized steel base on the roof, indoor unit with plasma filter as indicated on drawings to be tight installed completed with all necessary supports, hangers, drain pipes from indoor unit to the nearest floor drain, (PVC Ø 2"), copper pipes , sleeves, thermostat , and all required electrical cables according to drawings and engineers approval.</p> <p>CAPACITY : (12000 btu / hr).</p>	No.	1	600
1.5	<p>Extract Fans</p> <p>Supply, left to position, install, test & commission, (US or European made) such as S&P, SODECA or EQ. , (Exhaust air) centrifugal type fans complete with double skin box, price shall include all necessary & required electrical connections and cables (have 3-phase 4 pole), control system to controller fan with AC system , isolation switches, louvers, fittings accessories, supports(G.ST BASE), hangers and all works upon completing the work as per specifications, drawings, ASHRAE, ARI, NFPA codes & standards and Engineer satisfaction.</p>			
1.5.1	(1000 CFM) with static pressure 80 Pa	No.	2	500



No.	Description	Unit	Qu	1/1 شركة طلال مرتجى السعر بالدولار
1.6	Supply, install, test, and commission insulated galvanized sheet ducts (min. thick : 0.7 mm), with a proper gages as specified by SMACNA for Supply, Return, including 2" rock wool insulation and with aluminum foil, 24kg/m3 all accessories, galvanized ' L' angle hangers (2x40x40), with 10mm rods, bolts, flexible connector, with inner isolation duct liner for at least 3m length from unit, to be connected to the DSU units with flixable conniction , price must including opposite volume damper all the requirements according to SMACNA and other relevant international standards, drawings, and Engineers instructions.	M2	80	40
1.6.1	Ditto , BUT WITHOUT INSULATION	M2	80	30
1.7	<p style="text-align: center;">Air Distributing Equipment</p> Supply, Install, test, and commission anodized finish 4 ways square aluminum Ceiling Diffusers for supply air KES KLima, Yaad Type or equivelan. Price should include plenum boxes with inner isolation and oppositte blade. Noise Rating Should not exceed 40db all according to SMACNA and other relevant international standards, drawings, and Engineers instructions, Neck Size: 375x375mm, Face size:600x600mm, Plenum Box:425*425mm	No.	16	30



No.	Description	Unit	Qu	1/1 شركة طلال مرتجي السعر بالدولار
1.8	Supply, Install, test, and commission anodized finish 4 ways square aluminum Ceiling Return air grill. Noise Rating Should not exceed 40db all according to SMACNA and other relevant international standards, drawings, and Engineers instructions, Face size:600x600mm	No.	8	100
TOTAL Bill No. 10 (Mechanical Works				66480\$
Note: All relevant specifications requirements, drawings, and details are to be taken into account.				

وأنتهت اللجنة أعمالها بالتوقيع على المحضر،،،

رئيساً
أحمد حسن الشنطي

عضواً
جبر حجازي

عضواً
أيمن الخالدي

عضواً
فاطمة عوض

عضواً مراقباً
إيهاب الرئيس

